BRUHAT BANGALORE MAHANAGARA PALIKE

BILL OF QUANTITIES (BOQ)

Name of Work : Pot hole filling to Roads in Ward No.05 (Jakkur) Byatarayanapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Issued to Technical Manager , KRIDL	
				In Figures	In Words
1	3684.64	KSRRB- M 3000-2: Making up loss of of Material/irregulatities on shoulder ot the design level by adding fresh approved soil and compacting it with appropriate equipment complete as per s[ecifications. MORTH Specification No. 3003 (Page No. 265/ Item No.35.2, PWD SR 2018-19	Sqm	29.68	Rupees Twenty Nine and Sixty Eight Paise Only
2	552.70	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification NO. 406, No. 170/ Item No. 20.18/ PWD SR 2018-19	Cum	2001.28	Rupees Two Thousand One and Twenty Eight Paise Only
3	3684.64	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm.KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.0 back filling the pot hole with bituminous material as per clause 500.4 campacting traimming and finishing the surface to form a smooth continuous surface all as per clause 3004.2 complete as per specifications MORTH Specification (Page No. 247/Itm No.35.5) PWD SR 2018-19	Sqm	365.70	Rupees Three Hundred Sixty Five and Seventy Paise Only

1. The work should be executed as per the specification and standard specified by the PWD & Other specifications of the Bangalore Mahanagara Palike and as directed.
2. The work should be carried out as per the directions and instructions of the concerned Engineer
3. The Contractor should maintain the quality of work as per the standard specifications.

8/03

Executive Engineer (Byatarayanapura)
Bruhath Bangalore Mahanagara Palike

I am prepared to take up the above work at the rates quoted by me in the Schedule 'B'.

8/03

CONTRACTOR

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010